

2nd & 3rd St. & Parkway Ave. Project Newsletter



Construction includes:

- Sanitary sewer collection system and service lines
- Water mains and service lines
- Storm sewer construction
- Street construction
- Driveway and turf restoration
- Private utility relocations

Construction schedule:

- Start: End of June
- Finish: End of October

Contractor:

- GM Contracting, Inc.
Lake Crystal, MN
- Contact: Mike Urban
Phone: 507-726-6433
Cell: 507-327-9269
Email:
murban@gmcontracting.com



Bolton & Menk, Inc.
Phone: 507-625-4171

Brian Malm, P.E.
Eagle Lake City Engineer
Cell: 507-381-7511
E-mail:
brianma@bolton-menk.com

Steven DenHerder
Construction Representative
Cell Phone: 507-380-2691

CURRENT AND UPCOMING WORK

GM Contracting has been working on sewer and water services along 2nd Street this week. As you know, recent rains have created muddy conditions and slowed construction. Next week they plan to finish the services as well as the storm sewer along 2nd Street. In addition, removals will begin on 3rd Street north of the RR tracks on Tuesday or Wednesday next week, depending upon the weather. Access to the alley between 2nd and 3rd Street will be maintained with gravel either from the 2nd Street entrance or the 3rd Street entrance.

SERVICE CONDITION UPDATE

After completion several of the sewer services along 2nd Street last week, it appears that most of the services are transitioning from clay tile to cast iron pipe at the right-of-way line and there has been little evidence of root intrusion in the cast iron pipe. If you have questions about your private service, please feel free to call Steve DenHerder at 380-2691 or Brian Malm at 381-7511.

WATER SERVICE CONNECTION ISSUES

When the new water service connections are made, there are often rust deposits or corrosion in the old pipe that is inadvertently broken loose. This can cause discoloration in the water coming from the faucets in your house for a period of time. To help prevent this, GM Contracting will flush the water system in your home by opening up an exterior hose bib (if available) and letting it run for several minutes. This typically takes care of the problem however, if you still notice discoloration in your water immediately following hookup of your water service, we suggest that you flush out your plumbing by letting a bathtub or other faucet run for several minutes.

CONSTRUCTION QUESTIONS

Questions regarding construction activities and schedule, access, water shut-downs, etc. should be directed towards the on-site construction representative Steven DenHerder at 507-380-2691.

Archive copies of older newsletters for this project are available on the web at: www.bolton-menk.com/clients/eaglelake/index.htm