



Neighborhood Informational Meeting 2020 Street & Utility Improvements

November 6, 2019



1

Introductions

Brian Malm, P.E.
Bolton & Menk, Inc.
City Engineer
Cell: 507-381-7511
brian.malm@bolton-menk.com

Derek Olinger, P.E.
Bolton & Menk, Inc.
Assistant City Engineer
Cell: 507-525-2685
derek.olinger@bolton-menk.com



2

Agenda


- Project Area
- Existing Conditions
- Proposed Improvements
- Cost Estimate & Financing
- Schedule & Next Steps
- Construction Issues
- Questions



3

Project Selection

- Infrastructure Management Plan – August 2019




Infrastructure Management Plan
City of Plainview, MN
August 2019

Submitted By:
Bolton & Menk, Inc.
2500 Pioneer Drive
Mankato, MN 56001
P: 507-426-4177
F: 507-426-4177




4

Project Location



5

Typical City Street



6

Existing Conditions Streets

- Hillcrest Second Subdivision
 - 36-ft wide street
 - 60-ft wide right-of-way
- 2nd Street Southwest
 - 36-ft wide street
 - 60-ft wide right-of-way
- Asphalt surface – poor condition
- Concrete curb and gutter – fair to poor condition
- Miscellaneous streets will be overlaid as a maintenance effort to prolong pavement life



7



Exhibit 1 – Street & Curb Condition, Hillcrest Second Addition



8



Exhibit 2 – Street Condition, Hillcrest Second Addition



9



Exhibit 3 – Pavement Condition, 2nd Street Southwest



10



Exhibit 4 – Pavement Condition, 2nd Street Southwest



11

Existing Conditions Storm Sewer

Hillcrest Second Addition

- Existing 12-inch and 15-inch reinforced concrete pipe
- Drainage discharges into the 10th Street Northwest ditch
- System is undersized – needs more inlets
- The catch basins at the intersection of 8th Street Northwest and 3rd Avenue Northwest are severely deteriorated and need to be replaced.

2nd Street Southwest

- Existing 15-inch reinforced concrete pipe to the North
- There is a highpoint approximately at 2nd Street Southwest and 4th Avenue Southwest where water drains north or south. Water draining south ultimately discharges into MnDOT (TH 42) right-of-way.



12

Existing Conditions Sanitary Sewer

- Systems are approximately 50 years old
- 8-inch vitrified clay pipe
- Mineral deposits, offset joints, pipe sags, broken and damaged pipe, and blockages
- Manholes with evidence of infiltration
- Infiltration – increases flows, increases backup and bypass risk, increases pumping costs
- Shallow depths – Approximately 6-feet deep at the South end of 2nd Street SW



13

Existing Conditions Watermain

- Systems are approximately 50 years old
- 4-inch, 6-inch, and 8-inch cast iron pipe (CIP)
- CIP of this age is typically brittle, corroded, susceptible to breaks, and reduced in diameter due to mineral buildup
- History of watermain breaks along 2nd Street SW
- 4-inch pipe is undersized for fire protection



14


Proposed Conditions Streets

- 36-ft wide – allows for two 10-ft traffic lanes and 8-ft parking lanes on both sides (standard residential street width)
- Asphalt surfacing, concrete curb and gutter, concrete driveway aprons
- 5-ft concrete sidewalks with ADA pedestrian ramps on 2nd Street SW
- OPTIONAL 5-ft sidewalks for the Hillcrest Second Addition



15

Proposed Conditions Streets



16

Proposed Conditions Storm Sewer




- New 12-inch to 15-inch reinforced concrete pipe
- Additional inlets to take water faster
- Larger inlet grates
- 6-inch perforated subdrain with sump pump service stubs



17

Proposed Conditions Sanitary Sewer & Services



- 8" Diameter PVC Pipe
- Concrete Manholes
- 4" Services to Property Line
- Watertight System
- Shallow depths will remain
- Insulation provided for pipe and services with less than 7-ft of cover



18

Proposed Conditions Watermain & Services




- 8" Diameter PVC
- 1" Copper Services to Property Line (w/ Curb Stop)
- New Hydrants
- New Valves




19

Proposed Conditions




20

Proposed Conditions



21

Proposed Conditions



22

Other Utilities

- Communications (internet, phone cable)
- Natural Gas
- Electric
- Design to be coordinated with these systems



23

Estimated Costs

| Table 3 – Preliminary Cost Estimate | | | |
|---|-----------------------------|---|------------------------------|
| Item | Estimated Construction Cost | Estimated Engineering, Administration, and Financing Cost | Total Estimated Project Cost |
| Hillcrest Subdivision – Base Project | \$ 1,204,505.00 | \$ 301,200.00 | \$ 1,505,705.00 |
| 2 nd Street Southwest – Alt. No. 1 | \$ 677,307.50 | \$ 169,400.00 | \$ 846,707.50 |
| Misc. Mill & Overlays – Alt. No. 2 | \$ 694,315.00 | \$ 173,600.00 | \$ 867,915.00 |
| Total Estimated Project Costs | \$ 2,576,127.50 | \$ 644,200.00 | \$ 3,220,327.50 |



24

Financing

- We understand project will be financed using a bond sale repaid with:
 - Utility Funds
 - Tax Levy



25

Tentative Project Schedule Summary

| Table 3 – Project Schedule | |
|---|--------------------|
| Council Orders Preparation of Feasibility Report | 10/8/19 |
| Prepare Feasibility Report | 10/9/19 - 11/8/19 |
| Neighborhood Informational Meeting | 11/6/19 |
| Resolution Receiving Report | 11/12/19 |
| Resolution Ordering Improvement and Preparation of Plans and Specifications | 11/12/19 |
| Prepare Plans and Specifications | 11/13/19 - 3/10/20 |
| Neighborhood Informational Meeting | 2/18/20 |
| Resolution Approving Plans and Specifications and Ordering Advertisement for Bids | 3/10/20 |
| Advertise for Bids | 3/19/19 |
| Open Bids | 4/9/19 |
| Resolution Awarding Contract | 4/14/20 |
| Neighborhood Informational Meeting | 4/28/20 |
| Begin Construction | May 2020 |
| End Construction | June 2021 |




26

Council Decisions

- Decision to proceed with project determined at the Regular City Council Meeting on 11/12/19
- Need direction from the City on following items:
 - Extent of the project scope – Base Project + Alternates
 - Should sidewalk be added to Hillcrest Second Subdivision?



27



28



29



30



31



32

Construction Issues: Garbage & Recycling



- Same Day, Time, Location
- Contractor will work with garbage company
- Contractor will return receptacles



33

Construction Issues: Mail Delivery



- Contractor will work with Post Office
- Temporary mailboxes
- Location will be provided in newsletter
- Remove/Reinstall



34

Construction Issues: Water/Sewer Services

- Services replaced to R/W line
- Remaining service will be inspected, homeowner notified if replacement is required/recommended
- Replacement from R/W to home would be homeowner's responsibility
- Temporary Water



35

Construction Issues: Driveways



- Concrete Apron
- Replacement
- Concrete
- Bituminous/Asphalt



36

Construction Issues: Sidewalks



- Replacement
- Curing



37

Construction Issues: Turf Establishment



- Amended Topsoil
- Fertilizer & Seed
- Hydromulch
- 70% Growth
- Maintenance



38

Construction Communication: Newsletter



2020 Street & Utility Improvement Newsletter

October 21, 2019

Project Schedule:

Planning - Fall 2019

Design - Winter 2019/2020

Construction - Summer 2020

Overview

The City of Plainview is beginning to plan for the 2020 Street and Utility Improvement Project. Currently, the following two areas are being considered for full street and utility (sanitary sewer, watermain, and storm sewer) reconstruction:

- Hillcrest Second Addition
- 2nd Street Southwest

The location map on page 2 shows the areas being considered in more detail.

The first steps in the planning process include the completion of a topographic survey and the preparation of a Feasibility Report. The topographic survey work is scheduled to begin the week of October 28, 2019.

A neighborhood informational meeting is planned for Wednesday, November 6, 2019 at 6pm at City Hall to present information from the Feasibility Report and inform interested residents about the project being considered.




39

Construction Communication: Project Website

Coming Soon.....

City of Rushford – 2019 Street & Utility Reconstruction



Project Links

[Project Overview](#)
[Schedule](#)
[Contacts](#)
[Maps & Documents](#)
[Construction Updates](#)

Project Overview

The City of Rushford is beginning to plan for the 2019 Street and Utility Reconstruction Project within the following areas:

- E Grove Street (Walnut Street to Money Creek Street)
- N Burr Oak Street (E Grove Street to Circle Drive)
- Walnut Street (E Grove Street to E Rushford Avenue)
- Lamplighters Lane (Street improvements only)

Improvements will include complete replacement of bituminous pavement, curb and gutter, watermain and services, and sanitary sewer mains and services. Underground storm sewer will also be extended into the project area. The estimated cost of the proposed improvements is \$1.825 Million. A portion of the project costs will be assessed to adjacent properties in accordance with Chapter 429 of the Minnesota Statutes.



40

Construction Communication: RPR

- Bolton & Menk will have a Resident Project Representative on site every day construction is taking place.
- Question, Comments or Concerns should be directed to the RPR. Contact information will be provided.
- Limit questions to the contractor, staff isn't always completely in the loop on what is happening, RPR is.



41

Before You Leave

- Provide name and contact information on sign-in sheet
- More information on specific property impacts will be determined during design phase. We have tentatively scheduled a second Neighborhood Informational Meeting on 2/18/20.
- Specific concerns now, let us know.



42

Questions?

